

**PROJECT DESCRIPTIONS
FOR PROGRAM YEAR 2000
DISTRICT 2 - HAMILTON COUNTY
STATE CAPITAL IMPROVEMENT PROGRAM
(SCIP) PROJECTS**

- 1) Mt. Healthy – Seward Avenue Reconstruction - Estimated cost of \$650,000.00. Project is located between Adams Road to Compton Road, a total length of 1,800 feet. Project consists of removing the existing pavement to the subgrade, install new base material, install a new storm sewer system with vertical concrete curbs, overlay with asphaltic concrete. A grant of \$520,000.00 was approved for this project. Construction is to be complete by December 31, 2000.
- 2) Elmwood Place – Helen and Blade Street Reconstruction - Estimated cost of \$260,300.00. Project limits are as follows: Helen Street – from Blade Street to Township Avenue; Blade Street – from Helen Street to Vine Street, with a total length of 900 feet. Project consists of removing the existing pavement to the subgrade, install new base material, install a new storm sewer system with vertical concrete curbs, overlay with asphaltic concrete. A grant of \$130,150.00 was approved for this project. Construction is to be complete by June 1, 2001.
- 3) Cincinnati – Redbank Road Reconstruction - Estimated cost of \$1,005,400.00. Project limits are from Woodford Road to Zinsle Avenue. Project consists of rebuilding the roadway by removing deteriorated pavement and base, install new storm drainage facilities, curb, sidewalk, overlay with asphaltic concrete. A grant of \$502,700.00 was approved for this project. Construction is to be complete by June 30, 2002.
- 4) Forest Park – Northland Boulevard Repair and Resurfacing - Estimated cost of \$463,000.00. Project limits are from West Sharon Road east to Waycross Road. Project consists of grinding existing asphalt surface to concrete base, make partial and/or full depth pavement repairs of failed concrete joints, repair concrete curb and reconstruct existing drainage facilities. Resurface with asphaltic concrete and add curb ramps. A grant of \$185,200.00 was approved for this project. Construction is to be complete by June 9, 2001.
- 5) Delhi Township – Robben Lane Reconstruction – Estimated cost of \$475,000.00. Project limits are from Delhi Pike to Mt. Alverno Road between Greenwell and Pedretti Roads. Project consists of full depth removal of roadway and curbs, undercutting existing subgrade to obtain proper depth for replacement on a 10” stone base, 5” of asphaltic concrete, rolled concrete curb and gutter and 30” underdrains at all low points; sidewalk and driveway repair and associated utility work. A grant of \$380,000 was approved for the project. Construction is to be complete by September 15, 2001.
- 6) Cleves – Skidmore and Elliot Street Reconstruction - Estimated Cost of \$400,000.00. Project limits are as follows: Skidmore Street – from State Street to Morgan Street; Elliot Street – entire length of street, for a total length of 2,500 feet. Project consists of removing the existing pavement to subgrade, installing new base material, new storm drainage system with concrete vertical curbs, overlay with asphaltic concrete. A grant of \$360,000.00 was approved for the project. Construction is to be complete by June 1, 2001.

- 7) Sycamore Township – Kugler Mill Reconstruction - Estimated cost of \$712,000.00. Project consists of removing the existing pavement to subgrade, installing new base material, new

storm sewer system with vertical concrete curbs, driveway apron reconstruction, sidewalks, overlay roadway with asphaltic concrete. A grant of \$342,200.00 was approved for this project. Construction is to be complete by June 1, 2001.

- 8) Colerain Township – Compton Estates Reconstruction - Estimated cost of \$1,098,000.00. Project limits are as follows: Chopin Drive – entire length, 1,112 feet; Orangewood Drive – from Coogan to cul-de-sac, 1,755 feet. Project consists of removing existing pavement to subgrade, removing existing curbs, undercut subgrade as necessary, install new base material, new storm sewer system with vertical concrete curbs and pipe underdrains, install new curb ramps, overlay roadway with asphaltic concrete; adjust utility castings as necessary and water works items as needed. A grant of \$878,400.00 was approved for the project. Construction is expected to be completed by December 31, 2001.
- 9) Silverton – Stewart Road Drainage Improvements - Estimated cost of \$582,000.00. Project limits are from 3,150 feet south of the I-71 northbound off-ramp to 850 feet north of the I-71 southbound on-ramp, for a total length of 7,800 feet. Project consists of providing a new storm drainage system, replacing all inadequate storm conduit, remove and replace curb and gutters for the entire length of the project at a raised elevation to control storm water flow and direct it to inlets. A grant of \$465,600.00 was approved for this project. Construction is to be complete by June 1, 2001.
- 10) Anderson Township – Maycliffe Drive Improvements - Estimated cost of \$439,100.00. Project is for the entire length of Maycliffe Drive. Project consists of removal of existing roadway to subgrade, install new storm drainage system, install vertical concrete curbs, install new base material, overlay roadway with asphaltic concrete. A grant of \$219,550.00 was approved for this project. Construction is to be complete by June 1, 2001.
- 11) Madeira – Miami Avenue Resurfacing Phase II - Estimated cost of \$377,000.00. Project limits are from Euclid Road to Galbraith Road. Project consists of removal and replacement of existing curbs and driveway aprons, replace existing catch basins, shoulder and ditchline repairs, pavement repairs, overlay roadway with asphaltic concrete, add left turn signal to traffic signal at Loannes Drive. A grant of \$188,500.00 was approved for this project. Construction is to be complete by November 30, 2000.
- 12) North Bend – Sunset Avenue Reconstruction - Estimated cost of \$100,000.00. Project includes the entire length of the street. Project consists of removing the existing pavement to the subgrade, install new base material, install a new storm sewer system with vertical concrete curbs, overlay with asphaltic concrete. A grant of \$80,000.00 was approved for this project. Construction is to be complete by June 1, 2001.
- 13) Whitewater Township – Luther Lane Drainage Improvement - Estimated cost of \$170,000.00. Project limits are from approximately 300 feet from the terminus of Luther Lane west to Morgan Road for a total length of 300 feet. Project consists of excavation of the existing roadway to subgrade, replace catch basins, manholes and undersized culverts, install headwalls for culverts, repair drive aprons, install new base material for roadway, overlay roadway with asphaltic concrete, install guardrail. A grant of \$136,000.00 was approved for this project. Construction is to be complete by December 31, 2001.
- 14) Harrison – Harrison Avenue Rehabilitation Phase IV - Estimated cost of \$800,000.00. Project limits are from Broadway to State Road. Project consists of removing the existing surface, full and partial depth pavement repairs, widen pavement in downtown area with on-street parking to 42 feet, install new vertical concrete curb, reconstruct existing drainage structures, overlay

roadway with asphaltic concrete. A grant of \$400,000.00 was approved for this project. Construction is to be complete by December 31, 2001.

- 15) Cheviot – Washington Avenue Improvements - Estimated cost of \$377,430.00. Project limits are from Harrison Avenue on the south to Westwood Northern Boulevard on the north. Project consists of complete curb replacement and drive apron replacement; wearing course removal to reduce crown; pavement/base joint repair; curb ramp replacement, reconstruction of storm inlets, widen roadway from 25' b/b to 31' b/b between Homelawn and Smith, overlay roadway with asphaltic concrete. A grant of \$226,458.00 was approved for this project. Construction is to be complete by May 31, 2001.
- 16) Green Township – Perinwood Lane and Spechtview Drive Reconstruction - Estimated cost of \$315,400.00. Project limits are as follows: Perinwood Lane – from Spechtview to house #6819; Spechtview Drive – from Hearne Road to Perinwood Lane. Project consists of removal of existing pavement to subgrade, undercut and repair subgrade, rebuild catch basins, rebuild pavement with 13" crushed stone, overlay roadway with asphaltic concrete, reconstruct curb where needed. A grant of \$220,780.00 was approved for this project. Construction is to be complete by December 15, 2000.
- 17) Cincinnati – St. Lawrence/Rutledge Avenue Reconstruction - Estimated cost of \$905,720.00. Project limits are as follows: St. Lawrence – from Rapid Run Road to Rutledge Avenue; Rutledge Avenue – from St. Lawrence to St. Williams Avenue. Project consists of reconstruction of the existing pavement including removal of existing curb and pavement, and constructing new full depth asphalt pavement to handle the bus traffic utilizing these streets; new vertical concrete curb and underdrains will be installed also. A grant of \$452,860.00 was approved for this project. Construction is to be complete by December 31, 2001.
- 18) Green Township – Moonridge Drive (North) Reconstruction - Estimated cost of \$895,300.00. Project limits are from Lawrence Road to Bridgetown Road. Project consists of removal of existing pavement to subgrade, undercut and repair subgrade, rebuild catch basins, rebuild pavement with 13" crushed stone, overlay roadway with asphaltic concrete, reconstruct curb where needed. A grant of \$716,240.00 was approved for this project. Construction is to be complete by December 20, 2001.
- 19) Cincinnati – Vine Street Rehabilitation - Estimated cost of \$1,170,000.00. Project limits are from McMicken Avenue to Calhoun/Taft Street. Project consists of repairing and replacement of pavement and curbs, removal of existing surface, storm sewer repairs, overlay roadway with asphaltic concrete. A loan of \$585,000.00 was approved for this project. Construction is to be complete by December 31, 2001.

- 20) Cincinnati – Quebec Road Rehabilitation - Estimated cost of \$1,048,000.00. Project limits are from Glenway Avenue to Queen City Avenue. Project consists of repairing and replacement of pavement and curbs, removal of existing surface, storm sewer repairs, and overlay roadway with asphaltic concrete. A loan of \$524,000.00 was approved for this project. Construction is to be complete by December 31, 2001.

- 21) Cincinnati - State Avenue Rehabilitation - Estimated cost of \$1,201,530.00. Project limits are from West Eight Street to Queen City Avenue. Project consists of repairing and replacement of pavement and curbs, removal of existing surface, storm sewer repairs, and overlay roadway with asphaltic concrete. A loan of \$600,765.00 was approved for this project. Construction is to be complete by December 31, 2001.

- 22) Springfield Township – Covered Bridge Road Improvement - Estimated cost of \$684,000.00. Project limits are from 700 feet from the intersection of Miles Road at residence number 1558 to a point approximately 1,700 feet to the curb and gutter section of roadway in Covered Bridge Acres Subdivision. Project consists of removal of two large sycamore trees, widen roadway from 11 feet to a standard width of 20 feet for the entire length of the project. Removal of existing concrete ditches and replace with new storm sewer system including new vertical concrete curb. Removal of existing roadway surface, pavement repairs, install new 8” watermain, overlay roadway with asphaltic concrete. A loan of \$547,00.00 was approved for this project. Construction is to be complete by November 1, 2000.