

**PROJECT DESCRIPTIONS  
FOR PROGRAM YEAR 2002  
DISTRICT 2 - HAMILTON COUNTY  
STATE CAPITAL IMPROVEMENT PROGRAM  
(SCIP) PROJECTS**

- 1) Hamilton County – Jessup Road Roadway, Drainage, Walk Improvement - Estimated cost of \$2,250,000.00. Project limits are from Cheviot Road to Vogel Road, a total length of 5,900 feet. Project consists of widening Jessup Road to 28 feet, install a storm drainage system, replacing existing asphalt walks with concrete walks, resurfacing existing roadway with asphaltic concrete, add turn lanes at intersections. A grant of \$1,075,000.00 was approved for this project. Construction is to be complete by December 31, 2003.
- 2) Reading – Southern Street Storm Drainage Improvements - Estimated cost of \$549,550.00. Project limits are as follows: entire length of Southern Street; Jefferson Street from Southern to Oehler; Reading Road from Elizabeth Street to Southern Street; Elizabeth Street from Railroad tracks to Reading Road. Project consists of removing existing storm drains from combined sewers, install new 30" & 42" storm sewer, mill existing pavement and resurface with asphaltic concrete, remove and replace broken curb. A grant of \$439,640.00 was approved for this project. Construction is to be complete by June 1, 2003.
- 3) Wyoming – Elm Avenue Reconstruction - Estimated cost of \$775,000.00. Project limits are from Burns Avenue to East Mills Avenue. Project consists of full depth pavement removal and replacement, curb removal and replacement, add new storm catch basins, upgrade storm sewer system. A grant of \$387,500.00 was approved for this project. Construction is to be complete by June 30, 2003.
- 4) Columbia Township – Plainville Area Street Improvements - Estimated cost of \$530,000.00. Project is located off of Muchmore Road, north of State Route 50. Project consists of repairing failed areas of pavement, install new storm sewer system, reconstruct driveways and existing sidewalk, resurface with asphaltic concrete. A grant of \$371,000.00 was approved for this project. Construction is to be complete by July 15, 2003.
- 5) Cincinnati – Beekman/Harrison Street Improvements – Estimated cost of \$1,900,000.00. Project limits are Beekman Street traveling west from the Western Hills Viaduct through the "S" curve to the State Avenue/Queen City intersection. Project also covers Queen City Avenue, westbound, from Beekman Street/State Avenue to Harrison Avenue, and Harrison Avenue, eastbound, from Queen City to State Avenue. Project covers that portion of streets carrying traffic east and westbound to and from the Western Hills Viaduct in South Fairmont. Project consists of widening and reconstructing the roadway surface in the first part of the "S" curve with full depth concrete pavement, realign the intersection of Beekman Avenue, State Avenue and Queen City Avenue. Widen and resurface Queen City from Beekman/State to Harrison Avenue; full depth repairs and resurface Harrison Avenue from Queen City Avenue to State Avenue. Curb and sidewalk will be replaced where their condition or grading requirements warrant. A grant of \$1,710,000.00 was approved for the project. Construction is to be complete by December 31, 2003.

- 6) Anderson Township – Storm Sewer Detention & Pavement Reconstruction - Estimated Cost of \$1,595,400.00. Project limits are entire length of Sherman, Coolidge, Brooke and Shirmer Streets. Project consists of removing existing pavement to subgrade, undercut and remove unsuitable materials, install new storm sewers, new curbs, reconstruct pavement with gravel base, resurface with asphaltic concrete-1-. A grant/loan combination of \$1,515,630.00 was approved for the project. Construction is to be complete by December 31, 2003.
- 7) Green Township – Rackacres Drive Rehabilitation - Estimated cost of \$189,300.00. Project limits are from North Bend Road to west terminus. Project consists of crack and seat concrete pavement, repair base where necessary, repair all catch basins, curb repair where necessary, install underdrain, resurface with asphaltic concrete. A grant of \$94,650.00 was approved for this project. Construction is to be complete by November 30, 2002.
- 8) Green Township – Aurora Avenue Reconstruction - Estimated cost of \$740,375.00. Project limits are entire length of street from Bridgetown Road to Lawrence Road. Project consists of removal of existing pavement to subgrade, undercut and repair subgrade, rebuild catch basins and repair storm pipe where necessary, rebuild pavement with 13' crushed stone, geogrid fabric, resurface with asphalt concrete. A grant of \$591,625.00 was approved for the project. Construction is expected to be completed by December 31, 2003.
- 9) Cleves – State Route 264 Reconstruction, Phase I - Estimated cost of \$850,000.00. Project limits are US 50 to Pontious Road. Project consists of milling existing surface, pavement repairs, widen pavement to accommodate shoulder and turn lanes, resurface with asphaltic concrete, replace existing walks and curb, correct slip area, extend box culvert on Dowlin Street to remediate slip area. A grant of \$765,000.00 was approved for this project. Construction is to be complete by June 1, 2003.
- 10) Norwood – Montgomery Road Rehabilitation - Estimated cost of \$742,400.00. Project limits are from Wanda Avenue to the Norwood Lateral (SR 562). Project consists of removing existing surface, pavement repair, remove & replace catch basins, curb repair/replacement, handicap ramps, resurface with asphaltic concrete. A loan of \$742,400.00 was approved for this project. Construction is to be complete by June 1, 2003.
- 11) Springfield Township – Trapp Lane Reconstruction - Estimated cost of \$409,353.00. Project limits are from Springdale Road to the southern terminus. Project consists of correcting existing alignment, widening to 28 feet, improving the turning radius at Springdale Road, install new storm sewer system, new concrete curb and gutter, full depth pavement repairs, surface with asphaltic concrete. A loan of \$327,482.00 was approved for this project. Construction is to be complete by December 13, 2002.
- 12) Delhi Township – Rentz Place Reconstruction - Estimated cost of \$390,000.00. Project limits are from Foley Road to Fehr Road. Project consists of full depth removal of roadway and curbs, undercutting subgrade to obtain proper depth for replacement on a stone base, installation of rolled concrete curbs, underdrains, sidewalk and drive apron repair/replacement, surface with asphaltic concrete. A loan of \$312,000.00 was approved for this project. Construction is to be complete by September 15, 2003.

- 13) Norwood – Williams Avenue Resurfacing - Estimated cost of \$253,903.00. Project limits are from Forest Avenue to Edwards Road. Project consists of removing existing surface, replace concrete curbs, replace drive aprons, install new storm sewer inlets, install curb ramps, resurface with asphaltic concrete. A loan of \$253,903.00 was approved for this project. Construction is to be complete by September 10, 2003.
- 14) Colerain Township – Clara Avenue Reconstruction - Estimated cost of \$503,000.00. Project limits are from Galbraith Road to terminus, a distance of approximately 300 feet. Project consists of removing existing asphalt base, remove and replace existing drive aprons, widen roadway to 28 feet, install new curbs, storm sewer system, install new base, surface with asphaltic concrete. A loan of \$452,700.00 was approved for this project. Construction is to be complete by December 31, 2003.
- 15) Norwood – Elm Avenue Storm Sewer Improvements - Estimated cost of \$659,350.00. Project area located along Ridgeway Avenue and Woodlawn Avenue north of Maple Street to Elm Avenue. Project consists of removing existing pipe, reconstruct existing catch basins and manholes, install new upsized pipe, install new detention basin. A loan of \$659,350.00 was approved for this project. Construction is to be complete by October 1, 2003.