

**PROJECT DESCRIPTIONS  
FOR PROGRAM YEAR 2007  
DISTRICT 2 - HAMILTON COUNTY  
LOCAL TRANSPORTATION IMPROVEMENT PROGRAM  
(LTIP) PROJECTS**

- 1) **Green Township** – Rybolt Road Realignment - Estimated cost of \$1,988,035.00. Project is located in northwest Green Township. This is the second of two grants originally approved for program year 2006. Project includes relocation of Rybolt Road, which will be relocated to the east beginning at a point 400 feet south of Russell Heights Drive. It will again intersect Harrison Avenue at a point 1,500 feet south of the present intersection of Harrison and Rybolt, where Hearne Road and Harrison now intersect. The existing Rybolt Road will stay in service as the means for traffic from eastbound I-74 to access southbound Rybolt Road. A grant of \$1,151,227.00 was approved for this project for program year 2007. Construction is to be complete by November 30, 2009.
- 2) **Hamilton County** – Winton Road Improvement Phase III – Estimated cost of \$1,825,000.00. Project is located in Springfield Township; project limits are from Reynard Avenue to Fleming Road. Project includes widening of the existing pavement from 44 feet to 57 feet; full-depth pavement repair/replacement; overlay the pavement with asphaltic concrete; storm sewer system upgrade; replacement of curbs and sidewalks; construction of concrete intersection areas and bus stops. The completed project will be a uniform 57 feet wide with a continuous left-turn lane in the center. This is the second of two grants approved in program year 2006. A grant of \$876,000.00 was approved for this project for program year 2007. Construction is to be complete by December 31, 2009.
- 3) **Hamilton County** – Blue Rock Road Improvement - Estimated cost of \$2,142,544.00. Project limits are from Sheed Road to Galbraith Road. Project consists of widening the intersection at Livingston Road to create a left turn lane at all four legs of the intersection; profile and alignment changes, curbs and drainage structures along the entire length of the project; Galbraith Road will be widened to facilitate a left turn lane onto southbound Blue Rock Road, along with a new traffic control system; the entire project will be rehabilitated with full depth repairs and a structural overlay. A grant of \$1,049,847.00 was approved for this project. Construction is to be complete by June 30, 2009.
- 4) **Cincinnati** – Vine Street Widening – Estimated cost of \$1,450,000.00. Project limits are from the intersection of Vine Street and Nixon Street to the intersection of Vine Street and Erkenbrecher Avenue. Project includes widening Vine Street from 4 lanes (36' wide) to 5 lanes (58' wide) with a curb lane for bicycle travel and realigns the Erkenbrecher and Vine intersection; construct a new concrete base with asphalt surface, curbs, sidewalk, traffic signal and lighting. A grant of \$1,305,000.00 was approved for this project in both program year 2007 and program year 2008. Construction is to be complete by November 1, 2009.
- 5) **Harrison** – New Haven Road Improvements – Estimated cost of \$1,100,000.00. Project limits are from Harrison Avenue to the bridge over I-74. Project includes widening the existing roadway to 60 feet (5 lanes); install new vertical concrete curbs; lengthen turn lanes; access management, including reduction in number and size of curb cuts; mill pavement; overlay with asphaltic concrete. A grant of \$880,000.00 was approved for this project. Construction is to be complete by December 1, 2008.