

Rehabilitation of Winton Road Bridge B-0673
 Project No. 501709

Bid Date:
 November 29, 2018

Engineers Estimate: \$1,270,500.00

REF NO.	ITEM NO.	DESCRIPTION	UNIT	QUANT	UNIT	TOTAL
1	201	CLEARING AND GRUBBING	LS	1		
2	202	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN	LS	1		
3	202	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (EXISTING DIAPHRAGMS)	EA	20		
4	202	GUARDRAIL REMOVED	F	3825		
5	203	EMBANKMENT, AS PER PLAN	CY	100		
6	254	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN (2.5")	SY	2078		
7	442	ASPHALT CONCRETE SURFACE COURSE, TYPE B, 12.5mm, PG7-22 (448)	CY	480		
8	448	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG64-28	CY	87		
9	509	REINFORCING STEEL	LB	1814		
10	509	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL, AS PER PLAN	LB	200		
11	511	CLASS QC2 CONCRETE, SUPERSTRUCTURE	CY	34		
12	512	TYPE 2 WATERPROOFING	SY	1589		
13	513	STRUCTURAL STEEL, REPLACE END DIAPHRAGMS	EA	20		
14	514	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	SF	2902		
15	514	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT	SF	2902		
16	514	FIELD PAINTING OF STRUCTURAL STEEL, INTERMEDIATE COAT	SF	2902		
17	514	FIELD PAINTING OF STRUCTURAL STEEL, FINISH COAT	SF	2902		
18	514	FIELD PAINTING STEEL BRIDGE RAIL	SF	325		
19	516	STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC COMPRESSION SEAL	F	125		
20	516	REFURBISHING BEARING DEVICE, AS PER PLAN	EA	24		
21	516	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	LS	1		
22	519	PATCHING CONCRETE STRUCTURE, AS PER PLAN	SF	365		
23	519	PATCHING CONCRETE STRUCTURE, PARTIAL DEPTH PAVEMENT REPAIRS	SF	3000		
24	519	PATCHING CONCRETE STRUCTURE, FULL DEPTH PAVEMENT REPAIRS	SF	1500		

Engineers Estimate: \$1,270,500.00

Bid Date: November 29, 2018

Rehabilitation of Winton Road Bridge B-0673
Project No. 501709

REF NO.	ITEM NO.	DESCRIPTION	UNIT	QUANT	UNIT	TOTAL
		CONTINUED				
25	601	CONCRETE SLOPE PROTECTION, AS PER PLAN	SY	50		
26	601	TIED CONCRETE BLOCK MAT, TYPE 1, AS PER PLAN	SY	36		
27	606	GUARDRAIL, TYPE MGS	F	3825		
28	606	ANCHOR ASSEMBLY, TYPE E	EA	10		
29	606	ANCHOR ASSEMBLY, TYPE T	EA	10		
30	607	FENCE, TYPE CLT, AS PER PLAN	F	300		
31	613	LOW STRENGTH MORTAR BACKFILL, AS PER PLAN	CY	40		
32	614	MAINTAINING TRAFFIC	LS	1		
33	614	WORK ZONE IMPACT ATTENUATOR (BIDIRECTIONAL)	EA	8		
34	622	PORTABLE BARRIER, 32"	F	1670		
35	622	PORTABLE BARRIER, 32", BRIDGE MOUNTED	F	650		
36	624	MOBILIZATION	LS	1		
37	659	TOPSOIL	CY	24		
38	659	SEEDING AND MULCHING	SY	140		
39	659	REPAIR SEEDING AND MULCHING	SY	7		
40	659	COMMERCIAL FERTILIZER	LBS	40		
41	659	WATER	MGAL	1		
42	SPL	PERFORMANCE BOND	LS	1		
		CONTINGENCY AMOUNT				\$115,500.00
		TOTAL FOR PROJECT				\$
		CONTRACTOR'S NAME:				
		CONTRACTOR'S ADDRESS:				