

**2019 Sidewalk Repair/Replacement
Program
Anderson, Colerain, Columbia and Springfield Townships**

Bid's Taken: May 9, 2019
Eng. Estimate: \$66,930.00
Project No. 501901

REF NO.	ITEM SPEC.	DESCRIPTION	UNIT	QUANT	UNIT COST	TOTAL
ROADWAY GENERAL ITEMS						
1	452	7" P.C.C.P. FOR DRIVEWAY	SQ. FT.	974		
2	603	3" or 4" SCHEDULE 40 P.V.C. CONDUIT (DOWNSPOUTS)	L.F.	50		
3	608	5" P.C.C. SIDEWALK	SQ. FT.	3564		
4	608	CURB RAMP	EA.	1		
5	614	MAINTAINING TRAFFIC	L.S.	1		
SUB TOTAL FOR GENERAL ITEMS						
SUPPLEMENTAL ITEMS						
6	452	7" P.C.C.P. FOR DRIVEWAYS	SQ. FT.	100		
7	608	5" P.C.C. SIDEWALK	SQ. FT.	300		
8	608	CURB RAMPS	EA.	1		
SUB TOTAL FOR SUPPLEMENTAL ITEMS						
OVER ALL TOTALS						
TOTAL BID FOR PROJECT \$ _____						
CONTRACTORS NAME: _____						
CONTRACTORS ADDRESS: _____						