

SUMMIT ROAD SLIDE CORRECTION
Project No. 501914

BID DATE:
AUGUST 29, 2019

ENGINEER'S ESTIMATE: \$235,000.00

REF NO.	ITEM SPEC.	DESCRIPTION	UNIT	QUANT	UNIT COST	TOTAL
		ROADWAY ITEMS				
1	201	CLEARING & GRUBBING, INCLUDING TREE REMOVAL	LS	1		
2	202	PAVEMENT REMOVED (ASPHALT)	SY	150		
3	202	GUARDRAIL REMOVED	F	150		
4	204	SUBGRADE COMPACTION	SY	550		
5	301	ASPHALT CONCRETE BASE, PG64-22	CY	35		
6	304	AGGREGATE BASE, AS DIRECTED BY ENGINEER	CY	25		
7	448	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	CY	20		
8	448	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	CY	20		
9	524	24" REINFORCED DRILLED SHAFTS, INCLUDING SONO TUBE	F	1066		
10	524	30" UNREINFORCED DRILLED SHAFTS	F	238		
11	524	30" REINFORCED DRILLED SHAFTS	F	544		
12	606	GUARDRAIL, TYPE 5 WITH STEEL POSTS	F	550		
13	606	ANCHOR ASSEMBLY, TYPE T	EA	1		
14	614	MAINTAINING TRAFFIC	LS	1		
15	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1		
16	659	SEEDING & MULCHING, INCLUDING COMMERCIAL FERTILIZER (12-12-12)	SY	500		
17	SPL	PERFORMANCE BOND	LS	1		
18	SPL	TEMPORARY EROSION CONTROL	LS	1		
19	SPL	UNDERCUTTING, AS DIRECTED BY ENGINEER	CY	100		
		CONTINGENCY AMOUNT				\$25,000.00
		TOTAL FOR PROJECT				\$
		CONTRACTOR'S NAME: _____				

		CONTRACTOR'S ADDRESS: _____				

