

**Anderson Ferry Resurfacing/Rehabilitation**

**Bid Date:  
October 17, 2019**

**Engineer's Estimate: \$860,000.00  
Project No. 501906**

REF NO.	ITEM SPEC	DESCRIPTION	UNIT	QUAN	UNIT COST	TOTAL
1	202	PAVEMENT REMOVED (CONCRETE DRIVES)	SY	175		
2	202	GUARDRAIL REMOVED	F	124		
3	254	PAVEMENT PLANING (3" ASPHALT)	SY	20900		
4	442	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE B. 12.5 mm, PG64-28, 448	CY	960		
5	442	ASPHALT CONCRETE SURFACE COURSE, TYPE B. 12.5 mm, PG70-22, 448	CY	960		
6	452	NON-REINFORCED CONCRETE PAVEMENT (7" DRIVES)	SY	175		
7	606	GUARDRAIL, TYPE MGS	F	124		
8	606	MGS ANCHOR ASSEMBLY TYPE E	EA	4		
9	611	CATCH BASIN ADJUSTED TO GRADE (RING)	EA	1		
10	611	CATCH BASIN ADJUSTED TO GRADE (BRICK & MORTAR)	EA	1		
11	611	STORM MANHOLE ADJUSTED TO GRADE (RING)	EA	2		
12	611	STORM MANHOLE ADJUSTED TO GRADE (BRICK & MORTAR)	EA	7		
13	611	SANITARY MANHOLE ADJUSTED TO GRADE (RING)	EA	5		
14	611	SANITARY MANHOLE ADJUSTED TO GRADE (BRICK & MORTAR)	EA	20		
15	611	WATER VALVE CHAMBER ADJUSTED TO GRADE (RING)	EA	3		
16	611	WATER VALVE CHAMBER ADJUSTED TO GRADE (BRICK & MORTAR)	EA	2		
17	614	MAINTAINING TRAFFIC	LS	1		
18	644	CENTERLINE ( 6" DOUBLE, SOLID, YELLOW)	F	5600		
19	644	STOP LINE, 24" WHITE	F	200		
20	644	EDGE LINE, 4" WHITE	F	11200		
21	644	CHANNELIZING LINE, 8'	F	750		

**Anderson Ferry Resurfacing/Rehabilitation**

**Bid Date:  
October 17, 2019**

**Engineer's Estimate: \$860,000.00  
Project No. 501906**

REF NO.	ITEM SPEC	DESCRIPTION	UNIT	QUAN	UNIT COST	TOTAL
22	644	CROSSWALK LINE, 12"	F	600		
23	644	CROSSWALK LINE, PIANO KEY	F	50		
24	644	LANE ARROWS	EA	10		
25	644	WORD ON PAVEMENT "SCHOOL"	EA	2		
26	SPL	PERFORMANCE BOND	LS	1		
27	SPL	REMOVE RAISED PAVEMENT MARKERS	EA	180		
28	SPL	FULL DEPTH REPAIR (ASPHALT)	SY	1900		
29	SPL	EXTRUDED CONCRETE CURB, TYPE G	F	500		
30	SPL	CONCRETE CURB REPAIR, AS DIRECTED BY ENGINEER	F	1000		
31	SPL	CONCRETE CURB & GUTTER REPAIR, AS DIRECTED BY ENGINEER	F	200		
32	SPL	DETECTOR LOOP	EA	14		
33	SPL	ADDITIONAL DRIVEWAY MODIFICATION	CY	50		
34	SPL	REHABILITATE EXISTING CATCH BASIN/INLET, COMPLETE	EA	6		
35	SPL	RECONSTRUCT EXISTING CATCH BASIN/INLET, COMPLETE	EA	3		
36	SPL	ASPHALT REJUVENATOR, "RECLAMITE" OR APPROVED EQUAL	SY	20900		
		<b>SUBTOTAL FOR PROJECT</b>				\$ _____
		<b>CONTINGENCY AMOUNT</b>				<b><u>\$80,000.00</u></b>
		<b>TOTAL FOR PROJECT</b>				\$ _____
		<b>CONTRACTOR'S NAME:</b> _____				
		_____				
		<b>CONTRACTOR'S ADDRESS:</b> _____				
		_____				
		_____				